
## TECHNICAL SHEET

## 'REDLINE' MASON'S PIN Réf.: 7162250001

## **Caracteristics**

USE For small forms. 10 mm square section, ideal for holding rulers or small forms. FORGED VALET Hot-forged valet, for a 100% forged peg. Strike zone. Base section: 10.5 mm. TIP So-called barleycorn tip: 35° angle of attack, 11° penetration angle. Hardening localized over 80 mm then tempering operation for high hardness of the working parts (50-56 HrC). Excellent attack even in difficult terrain and great longevity. QUALITY OF STEEL Steel with a high carbon content: C45 for the jack, C55 for the tip. The forging operation makes it possible to obtain an excellent fibering of the steel for increased resistance. Point sharpness, very good performance and excellent life. QUALITY OF FINISH Textured paint, epoxy, electrostatically applied and baked. Evenness of the paint surface. Surface impact and abrasion resistance. Made in Europe in our factories



## **Product data**

L mm	Ø mm	d mm	E mm	L mm	g Ž	G	Artikelnr.		EAN Code
250	10	35	7	120	322	G30	7162250001	10	3303807162047
300	10	35	7	120	361	G30	7162300001	10	3303807162061



**NOVALIA SAS** 2 rue de Bergognon 42500 LE CHAMBON F. FRANCE - www.novalia.pro

PEDDINGHAUS Handwerkzeuge In der Graslake 35 58332 Schwelm DEUTSCHLAND - www.peddinghaus.de NOVALIA SA Str. Narciselor nr.50 500251 - Brașov ROMÂNIA www.mob-ius.ro

NOVALIA ESPAÑA Portuetxe 51, of.204 20018 San Sebastián